

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work: Improvements to roads and drains at 10th Cross and other Cross at Manjunatha nagara ward No:14 in Bagalagunte

			Est. Cost Rs				30.00	Lakhs	
Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.141/L.19.1 PW, P & IWTD -SR 2015-16)								
		Cum	1	500.00	~~1.50~~	0.30	~~225.00~~	225.00	
			1	150.00	0.45	0.40	27.00		
							252.00	83.16	20956.00
	Basic Rate	77.00							
	Add Area Weightage 8%	6.16							
	Total	83.16							
2	Removing B.S.Slab of drain and stacking etc., complete Page No. 25/ Item No. 5.32/ PWD SR 2015-16								
		Sqm	1	150.00	1.35		202.50		
							121.50		
		Consider 60% Qty							
	Basic Rate	59.00					81.00	63.72	5161.00
	Add Area Weightage 8%	4.72							
	Total	63.72							
3	KSRRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/L.4.3) PWD - SR 2015-16)								
			2	150.00	0.30	0.15	13.50		
	Basic Rate	4695.00					13.50	5070.60	68453.00
	Add Area Weightage 8%	375.60							
	Total	5070.60							

Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
4	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC Cement @220 kgs with 20 mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @0.56 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well comated, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per , Specification NO KBS 4.1,4.2 Page No 13/ Item No 4 7/PWD SR 2015-16								
		Sqm	2	150.00	0.20	0.10	6.00		
	Basic Rate	5085.00					6.00	5491.80	32951.00
	Add Area Weightage 8%	406.80							
	Total	5491.80							
5	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.6) PW, P & IWTD - SR 2015-16)								
			2	265.00	0.20	0.10	10.60		
						0.15	15.90		58202.00
	Basic Rate	5084.00					15.90	5490.72	87302.00
	Add Area Weightage 8%	406.72					10.60		
	Total	5490.72							
6	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 25/ Item No.5.33/ PWD SR 2015-16								
		Sqm					Qty Vide Item No 2	121.50	78.84 9579.00
	Basic Rate	73.00							
	Add Area Weightage 8%	5.84							
	Total	78.84							
7	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick (P. 25 I. 5.31.1) Page No. 25/ Item No. 5.31.1/ PWD SR 2015-16								
		Sqm					Qty vied Item No 02	202.50	
							Deduct Availabe Qty Vide Item No 2	121.50	
	Basic Rate	614.00					81.00	663.12	53713.00
	Add Area Weightage 8%	49.12							
	Total	663.12							
8	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 25/ Item No. 5.27/ PWD SR 2015-16								

[illegible]

Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
		Sqm	1	500.00	~~1.50~~		~~750.00~~		~~24300.00~~
					~~1.20~~		~~750.00~~	32.40	24300.00
	Basic Rate	30.00					~~600~~		~~19140.00~~
	Add Area Weightage 8%	2.40							
	Total	32.40							
13	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. Specification No. KRBS 500-1 MORTH Chapter 5 Page No. 160/ Item No. 21.2/ PWD SR 2015-16								
	Sqm	1	500.00	5.50			2750.00		8910.00
							2750.00	3.24	8910.00
	Basic Rate	3.00							
	Add Area Weightage 8%	0.24							
	Total	3.24							
14	KSRRB 500-7: Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all Materials, labour, HOM of machineries complete as per specifications. MORTH Chapter 5 Page No. 160/ Item No. 21.7/ PWD SR 2009-10								
	Sqm	1	500.00	5.50			2750.00		
							2750.00	15.12	41580.00
	Basic Rate	14.00							
	Add Area Weightage 8%	1.12							
	Total	15.12							
15	Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50/75mm compacted thickness with 3.3% bitumen but excluding the cost of primer/tack coat with lead incl. cost of all materials, labour, HOM of machineries complete as per specifications with 80/100 grade bitumen using 40/60TPH capacity H.M.P with Mechanical paver Gr II (50/75mm) with 3.3% VG-30 Bitumen as per the directions of Engineer-in-charge of the work (PWDSR 2015-16, P.No.161, I No.21.11.6)								
	Cum	1	500.00	1.50	0.05		37.50		
	Basic Rate	5735.00					37.50	6193.80	232268.00
	Add Area Weightage 8%	458.80							
	Total	6193.80							

Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
16	Providing and laying bituminous concrete with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filter transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment. rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause no 500.9 complete in all respects complete as per specification no 509. using 40/60 TPH Capacity H.M.P With Mechanical paver Gr-II (30 mm to 45 mm) with 6% VG-30 Bitumen (p-164, lt 21.22.6) PWD SR 2015-16								
		Cum	1	500.00	5.50	0.045	123.75		
	Basic Rate	9095.00					123.75	9822.60	1215547.00
	Add Area Weightage 8%	727.60							
	Total	9822.60							
17	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 133 Item No. 17.1 PWD SR 2015-16								
		Cum	Qty Vide Item No. 1				252.00	84.50	21294.00
	Loading and Unloading	68.00							
	Lead 4 KMs	10.24							
		78.24							
	Area Weightage @ 8%	6.26							
	Total	84.50							
18	Quality control Test Charges 1%						L.S		30000.00
19	Miscellaneous and Unforeseen Charges						L.S. 29480.00	29480.00	380.00
								Total	3000000.00


CERTIFICATE:-

Assistant Engineer
Ward-14

ನಂ. CE/02/AE/66 ದಿನಾಂಕ : 08-04-2016.
 ರೂ. 3000000/- ರೂ. ಮೂವತ್ತು ಲಕ್ಷಗಳು
ಗೃಹ
 ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
 ಮುಖ್ಯ ಅಭಿಯಂತರರು
 ಬಿ.ಬಿ.ಎಂ.ಸಿ.
 ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Name of work :- Improvements to roads & drains
at 10th cross and other cross roads at
Mannunatha Nagar Ward no 14, Bagalur.

AN




S.N. S.

ಸಹಾಯಕ ಸರ್ಕಾರಿ ಎಂಜಿನಿಯರ
ಟಿ.ದಾಸರವಳ್ಳಿ, ತಾಪ-ವಿಭಾಗ
ಬಾಗಲಗುಂಟೆ, ಬಿಜಿಎಂಪಿ
ಬೆಂಗಳೂರು

Power of wall: - Dry pack & rocks and chases
at 10th Cm & 5th Cm at
Maximum layer w. no. 4. Bagel

25022020
25022020



[Signature]

ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಅಧೀನದಲ್ಲಿ
ಬಿ.ವಾಸುದೇವ್ ಕುಮಾರ್-ವಿಭಾಗ
ಪಾಲಕರು, ಬಿ.ವಾಸುದೇವ್
ಬೆಂಗಳೂರು